



SpECtite PVC Waterstops

INTERNAL AND EXTERNAL FIXED PVC WATERSTOP

DESCRIPTION

SpECtite PVC Waterstop is a high grade PVC extrusion formulated to meet the highest performance specifications. SpECtite PVC Waterstops are supplied as straight lengths along with factory fabricated junction pieces to simplify layouts and site jointing.

TYPICAL USES

SpECtite PVC Waterstop provides a continuous network solution for sealing construction and movement joints in cast, in-situ concrete structures.

Typical uses include:

Water retaining

- Tanks, reservoirs and sewerage plants
- Swimming pools
- Oil storage tank bond walls
- Culverts, canals and dams

Water excluding

- Basements
- Underground car parks
- Buried storage tanks
- Retaining walls
- Bridge abutments
- Tunnels and subways

ADVANTAGES

- Unique design
- Full range of profiles
- Full range of factory fabricated junctions
- Continuous 4 valve network
- Reinforced edge flange with brass eyelets on internal sections for secure fixing
- Easy jointing system
- Approved for use in contact with potable water

RELEVANT STANDARDS


- Complies with US Corps of Engineers
- Specification CRD-C-572 and BS2571
- Test method BS2782:320A

TECHNICAL INFORMATION

PROPERTIES


VALUES

Profiles form	Extruded PVC profiles
Colour	Blue
Hydrostatic head	Up to 100m
Joint movement	Up to 12mm
PVC Compound	14±2 N/mm ²
Tensile strength min.	
Elongation at break min.	300%
Shore A hardness	70±5






SPECTITE PVC WATERSTOP INTERNAL PROFILES

Internal Expansion Joint (IEJ) sections are used in expansion joints. The centre bulb allows for cyclical movement in the structure and has a flat top section for seating of expansion joint fillers and formwork.




Internal Construction Joint (ICJ) plain web sections are used in construction joints. Grout excluding fins are incorporated to give a positive area to locate formwork and control grouts loss.






EXTERNAL PROFILES

External Expansion Joint (EEJ) sections are used in expansion joints. The centre box allows movement accommodation and has a flat top section for easy seating of expansion joint fillers and formwork.



External Construction Joint (ECJ) sections are used in construction joints and incorporate grout excluding fins to give a positive area to locate formwork and control grout loss.




EEJ and **ECJ** sections incorporate a nailing flange with a reinforced edge to provide secure fixing that will resist tearing.

NOTE:


150mm wide sections and extra heavy duty (XHD) profiles are available if required. Please contact SpEC Technical Department for more details.

ECJ Kicker is an extended width profile to be used when a separate kicker is cast between floor slab and wall construction which spans the 2 joints formed.




TYPICAL DETAILS OF MOVEMENT/CONSTRUCTION JOINTS WATER RETAINING STRUCTURES


Expansion joint - wall




Formed contraction joint - wall




Induced partial contraction joint - wall




Expansion joint - floor




Formed contraction joint - floor






Induced partial contraction joint - floor




Details comply with BS8007. Design of concrete structures for retaining aqueous liquids.

WATER EXCLUDING STRUCTURES


Junction of wall and ground slab.



Floor - section



Wall - plan



Details comply with BS8102: 1990. Protection of structures from water from the ground.

SPECTITE PVC WATERSTOP STANDARD JUNCTION PIECES

Factory fabricated junctions are available for all SpECTite PVC Waterstop profiles. Flat junctions have a leg length of 230mm from centre line. Vertical or on edge junctions have a leg length of 75mm.

IEJ/ICJ

Flat mitre



Flat 3-way



Flat 4-way



Vertical T-piece



90° Edge mitre



EEJ/ECJ

Flat mitre



Flat 3-way



Flat 4-way



90° Edge mitre



EEJ/IEJ AND ECJ/ICJ

Vertical T-piece



90° Edge mitre





SITE JOINTING WELDING EQUIPMENT

Site jointing of SpECtite Waterstop is carried out utilising SpECtite metal jointing jigs and electric heater blades.

WIDTH OF WATERSTOP

For concrete members of 250mm or above, use the 250mm profile.
For concrete members less than 250mm thick, select the waterstop width to be equal to or greater than the width of the concrete wall or slab.

PACKAGING

SpECtite PVC Waterstop

300mm wide 10m rolls
250mm wide 15m rolls
200mm wide 15m rolls
150mm wide 20m rolls

SpECtite Heater Blades

110v and 220v, 350w blades are available.
Warning: Ensure that heater blades are earthed by the green/yellow wire.

HEALTH & SAFETY

Hot welding of PVC waterstop will liberate hydrogen chloride vapour which may exceed the operational exposure limit of 5 parts per million in confined still air spaces. A suitable respirator or forced ventilation should be provided in these situations.

Issue 21 : 01/2026

Whilst the information and/or specifications given are, to the best of our knowledge, true and accurate, no warranty is given or implied in connection with any recommendations or suggestions made by us, our representatives, agents or distributors as the conditions of use and labour involved are beyond our control.

If it is proven that the product does not perform as described in our TDS, SpEC's liability extends solely to the free replacement of product, once the claim has been accepted after due investigation by SpEC. SpEC will not entertain any claims involving any form of consequential costs or damages such as shipping costs, custom duties, damages to third parties, damages to structures, penalties from delay of a project or any other form of consequential damage.

SPECIALITY ENGINEERING CHEMICALS

PO Box 61347, Dubai, United Arab Emirates. Telephone: +971 4 883 6662, Fax: +971 4 883 7696
E-mail: info@spec.ae
www.spec.ae